# IOWA STATE UNIVERSITY



Department of Economics, Department of Electrical & Computer Engineering

## Report on:

**ERCOT PNNL Contract 401882:** *Start Date* 3/19/2018

## Development of an Integrated Transmission and Distribution Test System to Evaluate Transactive Energy Systems

### ISU Project Team:

PI Leigh Tesfatsion & Co-PI Zhaoyu Wang

**Grad Research Assistant: Swathi Battula** 

PNNL/ISU Web Conference, 11 January 2019

## **ERCOT Contract: Presentation Outline**

- Original Task/Milestone Schedule: M1-M3
- Updated Task/Milestone Schedule: M1-M3
- Summary of Work Done for Milestone M3.2
- Summary of Work in Progress for Milestone M3.2
- Test-case input/output data verifying that AMES V5.0 correctly refreshes initial DAM/RTM conditions in multiple-day runs

# **Original Task & Milestone Schedule**

Milestone	Date Due	Original Description
M1	May 31, 2018	5-zone model of the old ERCOT system, posted to a web repository.
M2	Sep 30, 2018	Nodal model of the new ERCOT system, posted to a web repository.
M3	Sep 30, 2018	Submitted conference or journal paper on this work.

## **Updated Task & Milestone Schedule**

Milestone	Date Due	Date Delivered	Fuller Descriptions of Actual Work
M1* DONE	May 31, 2018	June 5, 2018	Development of 8-Bus ERCOT model (with nodal locational marginal pricing); grid/load/gen data posted at PNNL repository
M2.1 DONE	Sept 30, 2018	August 1, 2018	Basic 8-Bus ERCOT Test System, implemented via AMES V3.1, posted at <a href="https://github.com/ITDProject/ERCOTTestSystem">https://github.com/ITDProject/ERCOTTestSystem</a>
M2.2 DONE	Sept 30, 2018	August 24, 2018	8-Bus ERCOT Test System (with wind power), implemented via AMES V3.2, posted at <a href="https://github.com/ITDProject/ERCOTTestSystem">https://github.com/ITDProject/ERCOTTestSystem</a>
M3.1 DONE	Sept 30, 2018	August 31, 2018	200-Bus ERCOT Test System (with wind power), implemented via AMES V3.2,  posted at

<sup>• \*</sup> M1 Modification (Ok'd by PNNL): For M1 we have skipped the modeling of the old (zonal) ERCOT system and instead directly worked to develop an 8-bus model of the new (nodal) ERCOT system.

<sup>• \*\*</sup> M3 Modification: Contract extension through Feb 28, 2019 received from PNNL on Dec 21, 2018, for completion of task M3

#### **Summary of Work Done for Milestone M3.2**

- ☐ Extension of AMES V5.0 Capabilities for Milestone M3.2
  - [DONE] Coding for Daily DAM SCUC optimization
  - [DONE] Coding for RTM SCED optimization every M minutes (M user specified).
  - [DONE] Coding for FNCS integration to enable network co-simulation.
  - [DONE] Detailed documentation for analytical DAM SCUC/SCED optimization in AMES V5.0
  - [DONE] Basic documentation for AMES V5.0, including a detailed list for all parameters/flags and initial state variables that need user configuration.

### Summary of Work Done for Milestone M3.2 ... Continued

#### [ DONE ]

#### Modified `PSST' Code

- ➤ To ensure correct refreshing of initial DAM/RTM conditions for multiple-day runs.
- > To report DAM LMPs and GenCo Commitments back to the user.
- To read 'startup' and 'shutdown' cost components from AMES
- To produce output messages related to solver, e.g. status of the solver, termination condition of the solver
- ➤ To include the parameter 'Maximum Time Limit' to allow the solver to terminate after the prescribed time has elapsed

#### Verification Tests Done

- Verified 'DAM SCUC' outcomes for their correctness for simple test cases
- ➤ Verified 'RTM SCED' outcomes for their correctness for simple test cases with RTM running every five minutes (i.e., M=5)
- Verified that AMES V5.0 runs for multiple days
- Verified that all the cost components from AMES are read correctly into the SCUC formulation

### **Summary of Work in Progress for Milestone M3.2**

#### [IN PROGRESS] Additional Verification Checks for AMES V5.0 Code

- Additional DAM/RTM verification test cases are being formulated and conducted.
  - Example: Formulation of test cases with varied generator production cost coefficients and minimum generating capacity that permit validation of production cost component modeling for the SCUC optimization
- Need to ensure outcomes are reported properly back to the user. Additional data that need to be written to '.out' file are: RTM LMPs, RTM GenCo commitment data, DAM/RTM power flow data, LMP true costs, and generator profit/propensity data.
- ➤ Detailed verification of PSST code for validating SCUC optimization formulation, including both objective function and constraints.

#### [IN PROGRESS] Further Cleaning Up of AMES V5.0 Code

Current code includes unused functions that need to be removed.

### **Verification Test Case 1: Input Data**

**8BusTestCase1**: A test case to verify correct refreshing of initial DAM/RTM conditions

Some of the *input data* given in 8BusTestCase1.dat are presented below.

	1		
8BusTe	stCa	se1.dat	

// Name	ID	atBus	FCost	а	b	capL	capU	InitMoney	
GenCo1	1	1	0.0000	10.0000	0.0050	100	1000	1000000.0000	
GenCo2	2	2	0.0000	11.0000	0.0060	90	1000	1000000.0000	
GenCo3	3	3	0.0000	12.0000	0.0070	80	1000	1000000.0000	
GenCo4	4	4	50000	13.0000	0.0080	100	1000	1000000.0000	
GenCo5	5	5	50000	14.0000	0.0090	100	1000	1000000.0000	
GenCo6	6	6	50000	20.0000	0.0091	100	1000	1000000.0000	
GenCo7	7	7	50000	20.0000	0.0092	100	1000	1000000.0000	
GenCo8	8	8	50000	20.0000	0.0093	100	1000	1000000.0000	

#GenDataEnd

#GenDataStart

#ScucInputDataStart

// Name	PowerT0 U	nitOnT0	MinUpTime	MinDownTime N	IominalRampUp	NominalRampDown S	StartupRampLim	ShutdownRampLir	m Schedule	Schedule2	
GenCo1	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo2	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo3	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo4	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo5	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo6	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo7	1000.0000	1	0	0	0	0	0	0	1	1	
GenCo8	1000.0000	1	0	0	0	0	0	0	1	1	>
#ScucInnut	tDataEnd									C	)

### **Verification Test Case 1: Input Data ... Continued**

**8BusTestCase1**: A test case to verify correct refreshing of initial DAM/RTM conditions
Some of the *input data* given in 8BusTestCase1.dat are presented below.

8BusTestCase1.dat

#L	SEDataF	ixedl	Demand	Start								
//	Name		ID	atBus	H0	H1	H2	H3	H4	H5	H6	H7
	LSE1	1		1	1200	2200	3200	4200	200	200	200	200
	LSE2	2		2	200	200	200	200	200	200	200	200
	LSE3	3		3	200	200	200	200	200	200	200	200
	LSE4	4		4	200	200	200	200	200	200	200	200
	LSE5	5		5	200	200	200	200	200	200	200	200
	LSE6	6		6	200	200	200	200	200	200	200	200
	LSE7	7		7	200	200	200	200	200	200	200	200
	LSE8	8		8	200	200	200	200	200	200	200	200
//	Name		ID	atBus	H8	H9	H10	H11	H12	H13	H14	H15
	LSE1	1		1	200	200	200	200	200	200	200	200
	LSE2	2		2	200	200	200	200	200	200	200	200
	LSE3	3		3	200	200	200	200	200	200	200	200
	LSE4	4		4	200	200	200	200	200	200	200	200
	LSE5	5		5	200	200	200	200	200	200	200	200
	LSE6	6		6	200	200	200	200	200	200	200	200
	LSE7	7		7	200	200	200	200	200	200	200	200
	LSE8	8		8	200	200	200	200	200	200	200	200
//	Name		ID	atBus	H16	H17	H18	H19	H20	H21	H22	H23
	LSE1	1		1	200	200	200	200	200	200	200	200
	LSE2	2		2	200	200	200	200	200	200	200	200
	LSE3	3		3	200	200	200	200	200	200	200	200
	LSE4	4		4	200	200	200	200	200	200	200	200
	LSE5	5		5	200	200	200	200	200	200	200	200
	LSE6	6		6	200	200	200	200	200	200	200	200
	LSE7	7		7	200	200	200	200	200	200	200	200
	LSE8	8		8	200	200	200	200	200	200	200	200
#L	SEDataF	ixedl	Demand	lEnd								

### **Verification Test Case 1: DAM Output Data**

➤ **8BusTestCase1:** A test case to verify correct refreshing of initial DAM/RTM conditions Some of the **DAM output data** reported in the output files xfertoames.dat and ReferenceModel.dat are presented below.

Table 1: Generation ON/OFF Status

		GenCo1	GenCo2	GenCo3	GenCo4	GenCo5	GenCo6	GenCo7	GenCo8
	InitialCondition	1	1	1	1	1	1	1	1
D1	H1	1	1	1	0	0	0	0	0
D1	H2	1	1	1	1	0	0	0	0
D1	H3	1	1	1	1	1	0	0	0
D1	H4	1	1	1	1	1	1	0	0
D1	H5	1	1	0	0	0	0	0	0
D1		1	1	0	0	0	0	0	0
D1	H23	1	1	0	0	0	0	0	0
D1	H24	1	1	0	0	0	0	0	0
D2	InitialCondition	1	1	0	0	0	0	0	0

Table 2: Power Generation (p.u.)

		GenCo1	GenCo2	GenCo3	GenCo4	GenCo5	GenCo6	GenCo7	GenCo8
	InitialCondition	10	10	10	10	10	10	10	10
D1	H1	10	10	6	0	0	0	0	0
D1	H2	10	10	10	6	0	0	0	0
D1	H3	10	10	10	10	6	0	0	0
D1	H4	10	10	10	10	10	6	0	0
D1	H5	10	6	0	0	0	0	0	0
D1		10	6	0	0	0	0	0	0
D1	H23	10	6	0	0	0	0	0	0
D1	H24	10	6	0	0	0	0	0	0
D2	InitialCondition	10	6	0	0	0	0	0	0

### **Verification Test Case 1: RTM Output Data**

8BusTestCase1: Output demonstrating correct refreshing of initial RTM conditions.

Some of the *RTM output data* reported in the output files rt-unitcommitments.dat and RTReferenceModel.dat are presented below.

Table 3: Generation ON/OFF Status

		GenCo1	GenCo2	GenCo3	GenCo4	GenCo5	GenCo6	GenCo7	GenCo8
	InitialCondition	1	1	1	1	1	1	1	1
D2	H1	1	1	1	0	0	0	0	0
D2	H2	1	1	1	1	0	0	0	0
D2	H3	1	1	1	1	1	0	0	0
D2	H4	1	1	1	1	1	1	0	0
D2	H5	1	1	0	0	0	0	0	0
D2		1	1	0	0	0	0	0	0
D2	H23	1	1	0	0	0	0	0	0
D2	H24	1	1	0	0	0	0	0	0

Table 4: Power Generation (p.u.)

		GenCo1	GenCo2	GenCo3	GenCo4	GenCo5	GenCo6	GenCo7	GenCo8
	InitialCondition	10	10	10	10	10	10	10	10
D1	H1	10	4.2	8.0	1	0	0	0	0
D1	H2	10	4.2	0.8	1	0	0	0	0
D1	H3	10	3.8	8.0	1	1	0	0	0
D1	H4	10	2.2	8.0	1	1	1	0	0
D1	H5	10	6	0	0	0	0	0	0
D1		10	6	0	0	0	0	0	0
D1	H23	10	6	0	0	0	0	0	0
D1	H24	10	6	0	0	0	0	0	0

### **Verification Test Case 1: Summary**

#### 8BusTestCase1

#### Observations

- ✓ From Table 1's entries **D1-H24** and **D2-InitialCondition**, it can be seen that the refreshing of the initial ON/OFF status of each generator is done aptly.
- ✓ From Table 2's entries **D1-H24** and **D2-InitialCondition**, it can be seen that the refreshing of the initial power level for each GenCo is done aptly.
- ✓ From Table 1's entries **D1: H1-H24** and Table 3's **D2: H1-H24**, it can be seen that the GenCo ON/OFF commitment status levels determined on day **D1** are correctly carried over to the RTMs held on the following day (in this example **D2**).
- ✓ From Table 1's entries **D1**: **H1-H24** and Table 4's entries **D2**: **H1-H24**, it can be seen that GenCo ON/OFF commitment status levels are maintained correctly, and that GenCo commitments determined on **D1** for the balancing of net load on the next day **D2** are determined in the most economical way (i.e. the more costly generators are dispatched at their minimum generation output levels).

#### Conclusions

✓ Verified correct refreshing of initial DAM/RTM conditions for multiple-day runs.